SECTION 23 64 26 - AIR-COOLED CHILLERS

Project Beta - Hyperscale Campus Building B2, Roof. Chillers CH-1 and CH-2. Issued for Bid.

PART 1 - GENERAL

1.4 WARRANTY. A. Compressor warranty: 5 years parts and labor from startup.

PART 2 - PRODUCTS

2.2 PERFORMANCE. A. Net cooling capacity of each chiller shall be not less than 500 tons at AHRI 550/590 standard rating conditions.

2.2.B Full-load efficiency shall be not more than 1.20 kW/ton.

2.2.C Integrated part-load value (IPLV) shall be not more than 0.80 kW/ton.

2.2.D Refrigerant: global warming potential (GWP) not more than 700.

2.2.E Sound pressure level shall not exceed 78 dBA measured at 30 ft from the unit.

2.2.F Units shall operate at ambient air temperatures up to not less than 125 deg F.

2.3 ELECTRICAL. A. Power supply 460 V, 3-phase, 60 Hz with single-point power connection.

2.3.B Short-circuit current rating of the unit control panel: not less than 65 kA.

2.4 COMPONENTS. A. Compressors: variable-speed oil-free magnetic-bearing centrifugal, or variable-speed screw.

2.4.B Condenser fans: electronically commutated (EC) motors.

2.4.C Condenser coils: factory-applied corrosion-resistant e-coat.

2.4.D Integral air-side free-cooling coils with automatic changeover.

2.4.E Controls: native BACnet/IP interface to the BMS.

2.5 STRUCTURAL. A. Operating weight of each unit shall not exceed 30,000 lb (roof structural limit).

PART 3 - EXECUTION

3.1 TESTING. A. Factory performance test witnessed by the Owner per AHRI 550/590.

END OF SECTION